Work Order #21 Section 22B

ĺ	Address	Sidewalk 4" (SF)	Driveway 6" (SF)	Root Prunning (LF)	F&I Root Barrier (LF)	Replace Water MTR/Sewer Box/HH	F&I ADA Mat	Comments	
	SECTION - 22B - Colored Concrete - (Antique Cork)								
1	NW 52nd street (North side of street)	25							
2	NW 52nd street (North side of street)		270						
3	Paseo Drive (West side)	60						Demo Only 35SF	
4	Paseo Drive (West side)	235						Demo Only 90SF	
5	Paseo Drive (West side)	70							
6									
	TOTALS	390	270	0	0	0	0		

101-1B	Mobilization-Demobilization (Concrete Projects)	1	EA
102-1	Maintenance of Traffic (Concrete Projects) (Includes traffic control, pedestrian and vehicle access, signs, barricades, and flagger as per FDOT Standards, lighting, and steel plates if required)	30	DA
104-18	Inlet Protection System	1	LS
110-4-10	Remove existing Sidewalk (4" thick, 6" thick at driveways) (Includes removal and disposal of handicap ramps, mats, boxes, vaults, signs, poles, etc.)	74.00	SY
522-1	Construct new sidewalks (4" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	30.00	SY
522-2	Construct new sidewalks (6" thick at driveway) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	30.00	SY