

## Bid Sheet

### RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

PROJECT: RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services  
 LOCATION: (WO#23) Section 27

Contract Amount:	\$29,735.20
10% Contingency:	\$2,703.20
Funds by Resolution:	\$29,735.20

#### RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

Item No.	Description	Estimated Quantity	Unit	Unit Price	Total Bid
101-1B	Mobilization-Demobilization ( <b>Concrete Projects</b> ) (Includes dust control methods) (Scope of work: removal of existing concrete features, installation of new concrete features)	1	EA	\$ 5,000.00	\$ 5,000.00
102-1	Maintenance of Traffic ( <b>Concrete Projects</b> ) (Includes traffic control, pedestrian and vehicle access, signs, barricades, and flagger, as per FDOT Standards, lighting, and steel plates if required)	30	DA	\$ 200.00	\$ 6,000.00
104-18	Inlet Protection System	1	LS	\$ 150.00	\$ 150.00
110-4-10	Remove existing Sidewalk (4" thick, 6" thick at driveways) (Includes removal of handicap ramps, meter/valve box adjustment, and disposal of materials)	128	SY	\$ 20.00	\$ 2,560.00
110-22	Root pruning under existing sidewalk (Perpendicular length of sidewalk (Includes disposal of material)	35	LF	\$ 20.00	\$ 700.00
110-22-1	Furnish and Install Root Barrier - (Back/Front of sidewalk)	35	LF	\$ 20.00	\$ 700.00
425-7A	Replacement - Valve Box/Meter Box/Pull Splice Box - within sidewalk	4	EA	\$ 600.00	\$ 2,400.00
522-1	Construct new sidewalks (4" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	77	SY	\$ 72.00	\$ 5,544.00
522-2	Construct new sidewalks (6" thick at driveway) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	51	SY	\$ 78.00	\$ 3,978.00
<b>Sub-Total</b>					<b>\$ 27,032.00</b>

#### Contingencies Withdraws

No.	Description	Estimated Quantity	Unit		Total
1	10% Contingency	1.00	LS		\$ 2,703.20
<b>Sub-Total</b>					<b>\$2,703.20</b>

<b>Grand Total</b>	<b>\$ 29,735.20</b>
--------------------	---------------------

