

Work Order #24
Section 34

	Address	Sidewalk 4" (SF)	Driveway 6" (SF)	Root Prunning (LF)	F&I Root Barrier (LF)	Replace Water MTR/Sewer Box/HH	F&I ADA Mat	Comments
1	2100 NW 82nd Ave	50	50	15	15			
2	2224 NW 82nd Ave	100						
3	2236 NW 82nd Ave	25						
4	8200 NW 25th Street	35						West side of 82nd ave
5	2273 NW 82nd Ave		100					
6	2101 NW 82nd Ave	325		20	20			N.E. Corner
7	1701 NW 82nd Ave	25						
8	21st Street & 82nd Ave	75				1		S.E. Corner / 1ea. Vault
9	1904 NW 82nd Ave	125						
10	1900 NW 82nd Ave		50					
11	1598 NW 82nd Ave		125					+(plus) ... 30LF Curbing
12	1501 NW 82nd Ave	25						
13	1551 NW 82nd Ave	50				1		1ea. Vault
14	1629 NW 82nd Ave	25						
15	NW 82nd Ave just north of RR Tracks (east side of 82 Ave)		75					East side of 82nd ave
16	NW 14th Street & 82nd Ave		25					S.E. Corner
17	NW 82nd Ave just north of RR Tracks (west side of 82 Ave)		100					West side of 82nd ave
18	NW 82nd Ave between RR Tracks and NW 12th street	25						West side of 82nd ave
19	NW 82nd Ave between RR Tracks and NW 12th street							East side of 82nd ave
	TOTALS	885	525	35	35	2	0	

101-1B	Mobilization-Demobilization (Concrete Projects)	1	EA
102-1	Maintenance of Traffic (Concrete Projects) (Includes traffic control, pedestrian and vehicle access, signs, barricades, and flagger as per FDOT Standards, lighting, and steel plates if required)	30	DA
104-18	Inlet Protection System	1	LS
110-4-10	Remove existing Sidewalk (4" thick, 6" thick at driveways) (Includes removal and disposal of handicap ramps, mats, boxes, vaults, signs, poles, etc.)	158	SY
110-22	Root pruning under existing sidewalk (Perpendicular length of sidewalk (Includes disposal of material)	35	LF
110-22-1	Furnish and Install Root Barrier - (Back/Front of sidewalk)	35	LF
425-7A	Replacement - Valve Box/Meter Box/Pull Splice Box - within sidewalk	2	EA
520	Repair/Replace existing curbing (includes demo, form, & pour)	30	LF
522-1	Construct new sidewalks (4" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	99	SY
522-2	Construct new sidewalks (6" thick at driveway) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	59	SY