



Bid Sheet

RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

PROJECT: RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services
 LOCATION: (WO#24) Section 34

Contract Amount:	\$34,953.60
10% Contingency:	\$3,177.60
Funds by Resolution:	\$34,953.60

RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

Item No.	Description	Estimated Quantity	Unit	Unit Price	Total Bid
101-1B	Mobilization-Demobilization (Concrete Projects) (Includes dust control methods) (Scope of work: removal of existing concrete features, installation of new concrete features)	1	EA	\$ 5,000.00	\$ 5,000.00
102-1	Maintenance of Traffic (Concrete Projects) (Includes traffic control, pedestrian and vehicle access, signs, barricades, and flagger, as per FDOT Standards, lighting, and steel plates if required)	30	DA	\$ 150.00	\$ 4,500.00
104-18	Inlet Protection System	1	LS	\$ 250.00	\$ 250.00
110-4-10	Remove existing Sidewalk (4" thick, 6" thick at driveways) (Includes removal of handicap ramps, meter/valve box adjustment, and disposal of materials)	158	SY	\$ 45.00	\$ 7,110.00
110-22	Root pruning under existing sidewalk (Perpendicular length of sidewalk (Includes disposal of material)	35	LF	\$ 20.00	\$ 700.00
110-22-1	Furnish and Install Root Barrier - (Back/Front of sidewalk)	35	LF	\$ 25.00	\$ 875.00
425-7A	Replacement - Valve Box/Meter Box/Pull Splice Box - within sidewalk	2	EA	\$ 500.00	\$ 1,000.00
522-1	Construct new sidewalks (4" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	99	SY	\$ 74.00	\$ 7,326.00
522-2	Construct new sidewalks (6" thick at driveway) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	59	SY	\$ 85.00	\$ 5,015.00
Sub-Total					\$ 31,776.00

Contingencies Withdraws

No.	Description	Estimated Quantity	Unit	Total
1	10% Contingency	1.00	LS	\$ 3,177.60
Sub-Total				\$3,177.60

Grand Total	\$ 34,953.60
--------------------	---------------------