

Work Order #22
79 Ave Corridor (Section 22)

	Address	Sidewalk 4" (SF)	Driveway 6" (SF)	Root Prunning (LF)	F&I Root Barrier (LF)	Replace Water MTR/Sewer Box/HH	F&I ADA Mat	Comments
1	5485 NW 79th Avenue	30						East side of 79th avenue
2	5501 NW 79th Avenue							Install/Repair/replace - 20LF of existing curbing
3	5581 NW 79th Avenue	60				1		Utility Box/Vault
4	56th Street & 79th Avenue	60						N.E. Corner of intersection
5	5625 NW 79th Avenue	60						East side of 79th avenue
6	5640 NW 79th Avenue	60						West side of 79th avenue
7	7905 NW 54th street	60					1	Install/Repair/replace - 17LF of existing curbing
8	Approx. NW 52nd street & 79th Avenue (west side)	120						West side of 79th avenue
9	5015 NW 79th Avenue		210					East side of 79th avenue
10	5101 NW 79th Avenue	90				1		Utility Box/Vault
11	Approx. NW 52nd street & 79th Avenue (east side)	60						East side of 79th avenue
12	5241 NW 79th Avenue	30						East side of 79th avenue
13	Approx. NW 53rd street & 79th Avenue (east side)	100						East side of 79th avenue
14	4851 NW 79th Avenue		90					East side of 79th avenue
15	4815 NW 79th Avenue	30	180					East side of 79th avenue
16	4811 NW 79th Avenue		150					East side of 79th avenue
17	4805 NW 79th Avenue	60		10	10			East side of 79th avenue
18	7791 NW 46th street		60					East side of 79th avenue
19	7751 NW 46th street	30		5	5			East side of 79th avenue
20	4310 NW 79th Avenue (Doral Gardens Entrance)		170					(west side) Install/Repair/replace - 15LF of existing curbing
21	Approx. NW 48th street & 79th Avenue (west side)	30				1		West side of 79th avenue - Utility Box/Vault
22	48th street (Geneva Way) and 79th Avenue (west side)		90					West side of 79th avenue
23								
	TOTALS	880	950	15	15	3	1	

101-1B	Mobilization-Demobilization (Concrete Projects)	1	EA
102-1	Maintenance of Traffic (Concrete Projects) (Includes traffic control, pedestrian and vehicle access, signs, barricades, and flagger as per FDOT Standards, lighting, and steel plates if required)	30	DA
104-18	Inlet Protection System	1	LS
110-4-10	Remove existing Sidewalk (4" thick, 6" thick at driveways) (Includes removal and disposal of handicap ramps, mats, boxes, vaults, signs, poles, etc.)	204	SY
110-22	Root pruning under existing sidewalk (Perpendicular length of sidewalk (Includes disposal of material)	15	LF
110-22-1	Furnish and Install Root Barrier - (Back/Front of sidewalk)	15	LF
425-7A	Replacement - Valve Box/Meter Box/Pull Splice Box - within sidewalk	3	EA
520	Repair exsiting curbing (includes demo, form, & pour)	52	LF
522-1	Construct new sidewalks (4" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	98	SY
522-2	Construct new sidewalks (6" thick at driveway) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	106	SY
527-2	Curb Ramp Detectable Warning Surface (to install on ADA compliant curb ramp)	1.00	EA