Bid Sheet

RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

PROJECT: RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

LOCATION: WO#22 - 79 Ave Corridor (Section 22)

 Contract Amount:
 \$37,889.50

 10% Contingency:
 \$3,444.50

 Funds by Resolution:
 \$37,889.50

Item No.	Description	Estimated Quantity	Unit	ι	Jnit Price		Total Bid
101-1B	Mobilization-Demobilization (Concrete Projects) (Includes dust control methods) (Scope of work: removal of existing concrete features, installation of new concrete features)	1	EA	\$	5,000.00	\$	5,000.00
102-1	Maintenance of Traffic (Concrete Projects) (Includes traffic control, pedestrian and vehicle access, signs, barricades, and flagger, as per FDOT Standards, lighting, and steel plates if required)	30	DA	\$	150.00	\$	4,500.00
104-18	Inlet Protection System	1	LS	\$	250.00	\$	250.00
110-4-10	Remove existing Sidewalk (4" thick, 6" thick at driveways) (Includes removal of handicap ramps, meter/valve box adjustment, and disposal of materials)	204	SY	\$	20.00	\$	4,080.00
110-22	Root pruning under existing sidewalk (Perpendicular length of sidewalk (Includes disposal of material)	15	LF	\$	20.00	\$	300.00
110-22-1	Furnish and Install Root Barrier - (Back/Front of sidewalk)	15	LF	\$	25.00	\$	375.00
425-7A	Replacement - Valve Box/Meter Box/Pull Splice Box - within sidewalk	3	EA	\$	500.00	\$	1,500.00
520	Repair exsiting curbing (includes demo, form, & pour)	52	LF	\$	50.00	\$	2,600.00
522-1	Construct new sidewalks (4" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	98	SY	\$	70.00	\$	6,860.00
522-2	Construct new sidewalks (6" thick at driveway) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	106	SY	\$	80.00	\$	8,480.00
527-2	Curb Ramp Detectable Warning Surface (to install on ADA compliant curb ramp)	1	SY	\$	500.00	\$	500.00
Sub-Total	-			_		Ś	34,445.00

Contingencies Withdraws

No. Description Q	Quantity	Unit			Total			
1 10% Contingency	1.00	LS		\$	3,444.50			
Sub-Total \$3,444.50								

Grand Total \$ 37,889.50