

Bid Sheet

RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

PROJECT: WO#27
 LOCATION: Various - Storm Drain MH Cover Adjustments / Misc. Concrete

Contract Amount:	\$40,840.80
10% Contingency:	\$3,712.80
Funds by Resolution:	\$40,840.80

RFQ No. 2022-12 Sidewalk, Curb & Gutter and Miscellaneous Concrete Repair Services

Item No.	Description	Estimated Quantity	Unit	Unit Price	Total Bid
101-1B	Mobilization-Demobilization (Concrete Projects) (Includes dust control methods) (Scope of work: removal of existing concrete features, installation of new concrete features)	1	EA	\$ 7,000.00	\$ 7,000.00
102-1	Maintenance of Traffic (Concrete Projects) (Includes traffic control, pedestrian and vehicle access, signs, barricades, and flagger, as per FDOT Standards, lighting, and steel plates if required)	30	DA	\$ 250.00	\$ 7,500.00
425-5	Manhole Cover, Adjust, Utilities	7	EA	\$ 2,200.00	\$ 15,400.00
520-1	Remove Existing Concrete Sidewalk, Curb & Gutter, Valley Gutter, Raised Curb, Concrete Ribbon (Includes Disposal of Material)	94	SY	\$ 30.00	\$ 2,820.00
520-1-10	Construct New Concrete "F" Curb (as per FDOT Standards) Includes sub-grade material and prep.)	40	LF	\$ 60.00	\$ 2,400.00
522-1	Construct new sidewalks (4" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, etc.)	14	SY	\$ 72.00	\$ 1,008.00
110-22	Root pruning under existing sidewalk (Perpendicular length of sidewalk (Includes disposal of material)	25	LF	\$ 20.00	\$ 500.00
110-22-1	Furnish and Install Root Barrier - (Back/Front of sidewalk)	25	LF	\$ 20.00	\$ 500.00
Sub-Total					\$ 37,128.00

Contingencies Withdraws

No.	Description	Estimated Quantity	Unit	Total
1	10% Contingency	1.00	LS	\$ 3,712.80
Sub-Total				\$3,712.80

Grand Total	\$ 40,840.80
--------------------	---------------------

