



H & J ASPHALT, INC

Bid Sheet

RFQ No. 2022-13 Milling, Resurfacing, and Striping Construction Services

PROJECT: RFQ No. 2022-13 Milling, Resurfacing, and Striping Construction Services
 LOCATION: **WO#46 - City Section #33**

Contract Amount:	\$388,790.71
10% Contingency:	\$35,344.61
Total	\$388,790.71

RFQ No. 2022-13 Milling, Resurfacing, and Striping Construction Services

Item No.	Description	Estimated Quantity	Unit	Unit Price	Bid Total
Mobilization - Maintenance of Traffic					
101-1	Mobilization-Demobilization (Includes dust control methods)	1	LS	\$ 1,500.00	\$ 1,500.00
102-1	Maintenance of Traffic (Includes traffic control, pedestrian and vehicles access, signs, barricades, and flagger, as per FDOT Standards, lighting, and steel plates if required)	1	LS	\$ 1,500.00	\$ 1,500.00
ROADWAY ITEMS					
0104 18	INLET PROTECTION SYSTEM	1	LS	\$ 1,000.00	\$ 1,000.00
0110 4 10	REMOVAL OF EXISTING CONCRETE (CURBING, SIDEWALK, DRIVEWAY)	105	SY	\$ 50.00	\$ 5,250.00
0327 70 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	20,413	SY	\$ 2.20	\$ 44,908.60
0337 7 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	1225	TN	\$ 155.00	\$ 189,875.00
0425 5	MANHOLE, ADJUST	5	EA	\$ 800.00	\$ 4,000.00
0425 6	VALVE BOXES, ADJUST	5	EA	\$ 750.00	\$ 3,750.00
0425 7	VALVE BOXES, REPLACEMENT	2	EA	\$ 1,100.00	\$ 2,200.00
0425-12	CURB INLET TYPE - 9 (Frame Only); remove existing /replace new	12	EA	\$ 2,250.00	\$ 27,000.00
0520 1 10	CONCRETE CURB & GUTTER, TYPE F	100	LF	\$ 75.00	\$ 7,500.00
0520 2 4	CONCRETE CURB, VALLEY	355	LF	\$ 65.00	\$ 23,075.00
522-2	Construct new sidewalks (6" thick) (Includes cut and fill, sub-grade prep., ADA compliant handicap ramps, utility box(s) adjustments, sign(s) re-installtion, bench(s) re-installation, etc.)	4	SY	\$ 200.00	\$ 800.00
SIGNING AND PAVEMENT MARKINGS ITEMS					
0706 1 3	RAISED PAVEMENT MARKER, TYPE B	613	EA	\$ 5.00	\$ 3,065.00
0710 11101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	841	LF	\$ 1.00	\$ 841.00
0710 11112	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	197	LF	\$ 2.00	\$ 394.00
0710 11125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	154	LF	\$ 2.40	\$ 369.60
0710 11170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	33	EA	\$ 100.00	\$ 3,300.00
0710 11201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	9123	LF	\$ 1.00	\$ 9,123.00
0710 11224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	410	LF	\$ 4.00	\$ 1,640.00
0710 11131	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	153	EA	\$ 1.00	\$ 153.00
0711 16101	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6	841	LF	\$ 1.20	\$ 1,009.20
0711 11102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	197	LF	\$ 5.00	\$ 985.00
0711 11125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	154	LF	\$ 6.00	\$ 924.00
0711 11170	THERMOPLASTIC, STANDARD, WHITE, ARROW	33	EA	\$ 200.00	\$ 6,600.00
0711 16201	THERMOPLASTIC, STANDARD, OTHER SURFACES, YELLOW, SOLID, 6"	9123	LF	\$ 1.20	\$ 10,947.60
0711 11224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRONS	410	LF	\$ 3.60	\$ 1,476.00
0711 16131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	153	EA	\$ 1.70	\$ 260.10
Sub-Total					\$ 353,446.10

Contingencies Withdraws

No.	Description	Estimated Quantity	Unit	Unit Price	Scheduled Value
1	10% Contingency	1.00	LS		\$ 35,344.61
Sub-Total					\$35,344.61

Grand Total **\$ 388,790.71**