

**Weekley Asphalt Paving, Inc. Quote 07/09/2024**

**RFQ No. 2022-13 Milling, Resurfacing, and Striping Construction Services**

PROJECT: RFQ No. 2022-13 Milling, Resurfacing, and Striping Construction Services  
 LOCATION: WO#34 - NW 15th street bewteen 79th & 78th Avenues

Contract Amount:	\$94,771.55
10% Contingency:	\$8,615.60
<b>Total</b>	<b>\$94,771.55</b>

<b>RFQ No. 2022-13 Milling, Resurfacing, and Striping Construction Services</b>					
Item No.	Description	Estimated Quantity	Unit	Unit Price	Scheduled Value
<b>Mobilization - Maintenance of Traffic</b>					
101-1	Mobilization-Demobilization (Includes dust control methods)	1	EA	\$ 6,000.00	\$ 6,000.00
102-1	Maintenance of Traffic (Includes traffic control, pedestrian and vehicles access, signs, barricades, and flagger, as per FDOT Standards, lighting, and steel plates if required)	1	LS	\$ 5,000.00	\$ 5,000.00
<b>Milling and Resurfacing - Structural</b>					
104-18	Furnish and Install Erosion Control	6	EA	\$ 300.00	\$ 1,800.00
327-70-12	Milling of existing Asphalt Pavement, 1" Avg. depth	1,977	SY	\$ 6.30	\$ 12,455.10
337-7-82	Asphalt Concrete Friction Course, Traffic C, FC-9.5, PG 76-22	109	TN	\$ 275.00	\$ 29,975.00
425-7	Adjust - Valve Box	4	EA	\$ 650.00	\$ 2,600.00
520-1	Remove Existing Curb & Gutter, Valley Gutter, Concrete Ribbon (Includes Disposal of Material)	18	SY	\$ 183.00	\$ 3,294.00
520-1-09	Construct New Type "D" Concrete Curb (as per FDOT Standards) Includes sub-grade material and prep.)	96	LF	\$ 97.00	\$ 9,312.00
520-1-10	Construct New Type "F" Concrete Curb (as per FDOT Standards) Includes sub-grade material and prep.)	30	LF	\$ 130.00	\$ 3,900.00
<b>STRIPING</b>					
706-1-3	Raised Pavement Marker, Type B	23	EA	\$ 15.00	\$ 345.00
710-1	Painted Pavement Marking, Standard, White, Solid, 6"	1,165	LF	\$ 1.65	\$ 1,922.25
710-1-4	Painted Pavement Marking, Standard, White, Solid, 24"	35	LF	\$ 5.00	\$ 175.00
710-1-7	Painted Pavement Marking, Standard, White Solid Skip 6" (2' to 4')	63	LF	\$ 2.00	\$ 126.00
710-1-9	Painted Pavement Markings, Standard, White, Arrow	3	EA	\$ 150.00	\$ 450.00
710-1-10	Painted Pavement Marking, Standard, Yellow, Solid, 6"	734	LF	\$ 1.60	\$ 1,174.40
710-1-11	Painted Pavement Marking, Standard, Yellow Solid Skip 6" (2' to 4')	140	LF	\$ 3.20	\$ 448.00
711-1	Thermoplastic, Standard, White, Solid, 6"	1,165	LF	\$ 3.00	\$ 3,495.00
711-1-4	Thermoplastic, Standard, White, Solid, 24"	35	LF	\$ 12.00	\$ 420.00
711-1-7	Thermoplastic, Standard, White Solid Skip 6" (2' to 4')	63	LF	\$ 3.00	\$ 189.00
711-1-9	Thermoplastic, Standard, White, Arrow	3	EA	\$ 200.00	\$ 600.00
711-1-10	Thermoplastic, Standard, Yellow, Solid, 6"	734	LF	\$ 2.80	\$ 2,055.20
711-1-11	Thermoplastic, Standard, Yellow Solid Skip 6" (2' to 4')	140	EA	\$ 3.00	\$ 420.00
<b>Sub-Total</b>				<b>\$</b>	<b>86,155.95</b>